



Uttar Bihar Gramin Bank

Head Office, Kalambagh Chowk, Muzaffarpur

Tender Ref. No. HO/GAD/16/2023-24/1375

Dated: 06.03.2024

Financial Bid

(only empaneled vendors can quote)

Uttar Bihar Gramin Bank invites competitive rates from empaneled vendors for interior renovation of Board Room situated at Head Office Muzaffarpur. Please submit your competitive rates in closed envelope positively on or before 13.03.2024 till 3.00 P.M. The financial Bid will be opened on 13.03.2024 at Bank's head office at 3.30 P.M. in presence of committee members. All empaneled vendors who submit rate quotes are requested to remain present at the time of opening of tender. Please note that no separate invitation will be sent.

Terms and condition: -


Tenderers are advised to submit their rates in closed envelope under following terms and condition.

1. Quoted rates should be competitive. All quoted rates should be exclusive of GST. GST is payable additionally as per prevailing rules. Bidders have to quote for all items mentioned in attached Annexure, if the rate for any item is left blank, it will be treated as rejected.
2. If it is found that the material used is not same as mentioned in quotation, then the Bank has the right to reject the work and for such work done, Bank will not make any payment and said firm/company will be removed from the Bank's empaneled list.
3. The L1 rate will be decided as per annexure attached separately.
4. If the work is allotted to any vendor, he has to complete the job within stipulated time frame given by the Bank.
5. Please note that the measurement, quantity of different items are tentative and may increase/decrease as per the requirement of the Bank.
6. Please note that Bank will not provide any advance against work order.
7. Please note that before starting the work, material should be got verified by Architect/competent authority of Head Office.
8. No additional packing, transportation, delivery or installation charge will be paid by the bank.
9. Financial Bid in a closed envelope should be submitted to the "The General Manager, Uttar Bihar Gramin Bank, Head office, Muzaffarpur (842001) on or before 13.03.2024 till 3.00 P.M.
10. All work must be accomplished to the satisfaction of inspection committee/competent Authority.

**General Manager
Uttar Bihar Gramin Bank
Head Office- Muzaffarpur**

Specification of Interior works of Uttar Bihar Gramin Bank

S.No.	Item/Description	Unit	Quantity	Rate	Amount
1	Dismantalling of existing site nad removal of debris from premise	LS	1		
2	WALL PANELLING				
A	East Wall panelling of CEMENT SHEET 10MM (Full wall panelling)	SFT	237		
B	East wall panelling with WPC panel with aluminium support channel with thermocol	SFT	236		
	Mirror on East wall (white mirror 5mm) (As per design)	SFT	70		
C	West wall panelling with pvc fluted panel (As per design)	SFT	228		
D	South wall and north wall with fluted panel (As per design)	SFT	226		
E	North wall with t.v unit WITH PLY WORK OF 18MM ply framing finished with 1.25 mm thick laminate	SFT	126		
3	providig and fixing low height storage below tv unit made with 25 mm thick ply finished with 1 mm thick lamine on both side with one shelf	SFT	35		
4	Providing and fixing Planter made with 25 mm thick ply finished with 1 mm thck laminate	Sft	12		
5	Providing and fixing 32 mm thick flush door finished with 1 mm thick laminate along with vision panel	Nos	2		
6	CONFERENCE TABLE				
	Made with 19mm ply & unicolormica/pvc mica over the surface with white mat finish and glass in middle	SFT	96		
7	Flooring with italian finish with ginch skirting (4x2 tiles in kajariya)	SFT	440		



8	FALSE CEILING				
A	Saint globin gymsum sheet with gyproc chanel				
B	Baffle ceiling made with 12 mm thick Wpc board finished with laminate as approved by architect in charge	SFT	255		
C	Providing and applying three or more coats of best quality plastic emulsion paint of approved manufacture and	RFT	150		
d	Providing and applying 2 coats of birla white putty	Sft	500		
g	PANTRY DETAIL	Sft	500		
a	Providing and fixing pantry counter made with 25 mm thick waterproof ply finished with 1 mm thick from laminate from both side except refrigerator				
b	Providing and fixing overhead storage made with 25 mm thick ply finished with 1 mm thick laminate except oven	SFT	20		
c	Providing & fixing of stainless steel sink with proprietary ci brackets painted white, cp brass bottle trap, waste, union of standard pattern complete in all respects inclusive of cutting and making good the walls wherever required. (single drain board & single bowl)	SFT	20		
d	Providing & fixing of basin/ wall mounted faucet Swan neck sink cock for sink complete as per satisfaction of Project In charge.	Nos	1		
e	Providing & fixing, testing and commissioning of CP brass angle valve with strainer and CP wall flange, Nut and Washer etc. complete.	Nos	1		
f	Providing and fixing granite for counter top in Pantry counter	Nos	1		
g	Providing and fixing 25 mm thcik CPVc pipe for water supply	Sft	20		
h	Providing and fixing 50 mm Drain pipe	Rft	30		
10	Electrical work for conference room with DB, Power point, Down light	Rft	30		
		Sft	300		
	TOTAL				

- NOTE** 1. All work should be executed as per design and in supervision of architect.
2. Increment or decrement in material will be according to design.

