



Uttar Bihar Gramin Bank

Head Office, Kalambagh Chowk, Muzaffarpur

Tender Ref. No. HO/GAD/16/2023-24/1473

Dated: 13.03.2024

Financial Bid

(only empaneled vendors can quote)

Uttar Bihar Gramin Bank invites competitive rates for electrical work of Head Office from empaneled vendors for electric items which were not mentioned in commercial bid no. HO/GAD/15-2022-23/1354 dated: 27.02.2023 Please submit your competitive rates in closed envelope positively on or before 20.03.2024 till 3.00 P.M. The financial Bid will be opened on 20.03.2024 at Bank's head office at 3.30 P.M. in presence of committee members. All empaneled vendors who submit rate quotes are requested to remain present at the time of opening of tender. Please note that no separate invitation will be sent.

Terms and condition:-


Tenderers are advised to submit their rates in closed envelope under following terms and condition.

1. Quoted rates should be competitive. All quoted rates should be exclusive of GST. GST is payable additionally as per prevailing rules. Bidders have to quote for all items mentioned in attached Annexure, if the rate for any item is left blank, it will be treated as rejected.
2. If it is found that the material used is not same as mentioned in quotation, then the Bank has the right to reject the work and for such work done, Bank will not make any payment and said firm/company will be removed from the Bank's empaneled list.
3. The L1 rate will be decided as per annexure attached separately.
4. If the work is allotted to any vendor, he has to complete the job within stipulated time frame given by the Bank.
5. Please note that the measurement, quantity of different items are tentative and may increase/decrease as per the requirement of the Bank.
6. Please note that Bank will not provide any advance against work order.
7. Please note that before starting the work, material should be got verified by Architect/competent authority of Head Office.
8. No additional packing, transportation, delivery or installation charge will be paid by the bank.
9. Financial Bid in a closed envelop should be submitted to the "The General Manager, Uttar Bihar Gramin Bank, Head office, Muzaffarpur (842001) on or before 20.03.2024 till 3.00 P.M.
10. All work must be accomplished to the satisfaction of inspection committee/competent Authority.


General Manager
Uttar Bihar Gramin Bank
Head Office- Muzaffarpur



S.NO	DESCRIPTION	UNIT	RATE	AMOUNT
1	MAIN ELECTRICAL CUBICAL TYPE PANNEL			
	SUPPLY ERECTION CONNECTING TESTING AND COMMISSIONING OF CUBICAL TYPE PANNEL FABRICATED OUT OF CRCA SHEET, WALL MOUNTED TOTALLY ENCLOSED SWITCHBOARD OF UNIFORM WIDTH SUITABLE FOR USE OF 415 VOLTS, 3 PHASE 50 HZ COMPLETE AND HOUSED WITH COPPER BUS BAR EQUIPMENT AND THEIR ACCESSORIES INCLUDING SUPPLY AND FIXING OF BASE CHANNEL 100*50*6 MM AS REQUIRED AND WITH FOLLOWING INCOMMING AND OUTGOING SWITCHGEAR AS PER THE SPECIFICATION AND SCHEMATIC DIAGRAM POWDER COATED			
	SIZE OF PANNEL-39''*30''*12''(H*W*)			
	INCOMMER:			
	1 NOS 200 AMP TPN , 35 KA MCCB'S WITH MICROPROCESSOR BASED RELEASES FOR OVERCURRENT, SHORTCIRCUIT AND EARTH FAULT, ISOLABLE NEUTRAL ON INDICATOR 1 NO MULTIFUNCTION DIGITAL METER SHOWING ALL POWER PARAMETER WITH SELECTOR SWITCH MATCHING EAST RESIN CT'S	3 NOS		
	200 AMP MCCB 4 POLE			
	BUS BAR			
	A SET OF COPPER BUS BAR RATED FOR 200A AFTER CONSIDERING ALL NECESSARY DERATING 3 PHASE 4WIRE, 50HZ FOR MAIN LINE.			
	ALL INTERNAL WIRING WITH 10SQMM COPPER WIRE			
	OUTGOING			
	15 NOS OF 20 AMP 6KA DP MCB FOR INDIVISUAL ACS			
	OTHER ITEMS			
	1 LOT CONTROL COPPER WIRING			
	1 SET DESIGNATION PLATES			
	WITH ALL INTERNAL WIRING AND THIMBLE INCLUDED			
2	20A MODULAR INDUSTRIAL SOCKET	80 PCS		
3	MODULAR MCB 20A 6KA	40 PCS		
4	25 *4*6*1 Sq.mm SINGLE CORE COPPER WIRE	175 Mtr		
5	4*2*1.5*1 sq.mm copper wire	700 mts.		



Electricity Work (Extra)

S.NO	DESCRIPTION	UNIT	RATE	AMOUNT
01	PROVIDE FIXING MAIN ELECTRICAL CUBICAL TYPE PANNEL			
	SUPPLY ERECTION CONNECTING TESTING AND COMMISSIONG OF CUBICAL TYPE PANNEL FABRICATED OUT OF CRCA SHEET, WALL MOUNTED TOTALLY ENCLOSED SWITCHBOARD OF UNIFORM WIDTH SUITABLE FOR USE OF 415 VOLTS, 3 PHASE 50 HZ COMPLETE AND HOUSED WITH COPPER BUS BAR EUIPMENT AND THEIR ACCESSORIES INCLUDING SUPPLY AND FIXING OF BASE CHANNEL 100*50*6 MM AS REQUIRED AND WITH FOLLOWING INCOMMING AND OUTGOING SWITCHGEAR AS PER THE SPECIFICATION AND SCHEMATIC DIAGRAM POWDER COATED	01		
	SIZE OF PANNEL—39''*30''*12''(H*W*)			
	INCOMMER:			
	1 NOS 200 AMP TPN , 35 KA MCCB'S WITH MICROPROCESSOR BASED RELEASES FOR OVERCURRENT, SHORTCIRCUIT AND EARTH FAULT, ISOLABLE NEUTRAL ON INDICATOR 1 NO MULTIFUNCTION DIGITAL METER SHOWING ALL POWER PARAMETER WITH SELECTOR SWITCH MATCHING EAST RESIN CTs			
	200 AMP MCCB 4 POLE			
	BUS BAR			
	A SET OF COPPER BUS BAR RATED FOR 200A AFTER CONSIDERING ALL NECESSARY DERATING 3 PHASE 4WIRE, 50HZ FOR MAIN LINE.			
	ALL INTERNAL WIRING WITH 10SQMM COPPER WIRE			
	OUTGOING			
	15 NOS OF 20 AMP 6KA DP MCB FOR INDIVISUAL ACS			
	OTHER ITEMS			
	1 LOT CONTROL COPPER WIRING			
	1 SET DESIGNATION PLATES			
	WITH ALL INTERNAL WIRING AND THIMBLE INCLUDED			
02	PROVIDE FIXING 20A MODULAR INUSTRIAL SOCKET	1 PCS		
03	PROVIDE FIXING MODULAR MCB 20A 6KA	1 PCS		
04	PROVIDE FIXING 25 *4+6*1 Sq.mm SINGLE CORE COPPER WIRE	1 Mtr.		
05	PROVIDING & FIXING 16*2+6*1 Sq. SINGLE CORE COPPER WIRE	1 Mtr.		
06	PROVIDING & FIXING 10*2+4*1 Sq. SINGLE CORE COPPER WIRE	1 Mtr.		
07	PROVIDE FIXING 6*2+2.5*1 sq.mm copper wire	1 Mtr.		

